

American Society of Highway Engineers (ASHE) Transportation Project Development A Locality's Perspective

Presented by

W. Todd Minnix, PE

Chief, Transportation Design Division (TDD)

Fairfax Count Dept. of Transportation (FCDOT)

February 8, 2023





Transportation Project Development A Locality's Perspective

Agenda

- Brief Program Update
- Consultant Selection
- Project Development Issues QA/QC
- Project Overview- Richmond Highway Bus Rapid Transit (BRT)
 If we have time!





- Delays in Program Implementation
 - COVID funding stream uncertainty; not what we expected
 - Inflation significant impact
 - Overruns and 'overcommitment' particularly on Bike/Ped Program
 - Deferred/delayed implementation of a number of 'approved' projects
- Examples:
 - Old Courthouse Road/Besley Road
 - Original project estimate was \$3.3M
 - Current estimate is \$18M





- Aggressively pursuing other funding sources
 - Approx. 2,500 unfunded Bike/Ped projects alone
 - RAISE Grants unsuccessful on 1st attempt
 - Safe Streets for All (SS4A) \$30M/year for up to 5 years (unsuccessful)
 - NVTA Awarded \$336.2M in FY2022-2027 SYP for 6 projects (4 already underway)
 - SmartScale Round 5 pending CTB
- Board of Supervisors Approved \$100M in General Fund \$ for bicycle and pedestrian projects countywide \$30M already appropriated
 - Includes some funds for Maintenance and Safety
 - Initial List of 18 new Projects approved by BOS "Quick hit" projects
 - Working on list of 30+ new Projects and Funding for March BOS Meeting





- NVTA Awards \$336.2M
 - Fairfax County Parkway Widening Nomes Ct. to Route 123- \$108M (VDOT)
 - Route 1 Widening Mt. Vernon Mem. Highway to Sherwood Hall Lane -\$60.207M (VDOT)
 - Richmond Highway Bus Rapid Transit \$80M (FCDOT)
 - Soapstone Drive Extension Sunrise Valley Dr. to Sunset Hills \$73.79M (VDOT)
 - Seven Corners Ring Road (Phase I) \$4.2M (NEW) (FCDOT?)
 - 8 Battery Electric Buses for Fairfax Connector \$10M (NEW)





- Program Implementation Consultant Services/Contracts
- 95%+ of Design performed by On-Call Consultants
 - Transportation Design Division (TDD)
 - Nine (9) On-Call Firms in 3rd year of 5-year term
 - 3rd year expires October 2023
 - Anticipate issuing RFQ for next TDD On-Call in early Spring 2025
 - Pending Standalone Contracts
 - Route 1 Bus Rapid Transit Pre-Award Engineering Support, Independent Assurance (IA), Verification, Sampling and Testing (VS&T) services (essentially QA services during construction)
 - Anticipate RFQ in Winter 2024/2025





- Capital Projects and Transportation Planning Divisions (CPTED/TPD)
 - Nine (9) On-Call Firms in 5th year of 5-year term
 - Transportation Planning, Design and Engineering
 - Transportation Planning and Analysis (9)
 - Transportation Design and Engineering (8)
 - Transit Planning and Analysis (7)
 - <u>4th Year expired on 2/5/23</u>
 - Anticipate RFP/RFQ for next CPTED/TPD On-Call in Spring/Summer 2023






- Major Projects in Current Program:
 - Route 28 Widening (Design-Build) (LAP) Prince William County Line to Route 29 \$78.8M (CN Underway)
 - Lincoln Street Magarity Road to Old Meadow Road \$48M (Prelim. Design)
 - Shirley Gate Road Extension Fairfax County Parkway/Pope's Head Road Interchange to New Braddock Road – \$29M (Prelim. Design)
 - Balls Hill Road/Old Dominion Drive \$21M (Prelim. Design)
 - Wiehle Ave./W&OD Trail Grade Separation (LAP) \$14.3M (CN Awarded)
 - Cinder Bed Road Bikeway (LAP) \$15M (RW underway)
 - Mount Vernon Memorial Highway Walkway \$9.9M (CN underway)
 - Innovation Station Neighborhood Access \$8.1M (RW Phase pending)





Transportation Project Development










Transportation Project Development







Transportation Project Development



Rendering of Proposed Pedestrian Bridge Over Wiehle Avenue Looking North from Sunset Hills Road





Transportation Project Development



Innovation Station North Neighborhood Access





- Challenges Ahead:
 - Funding
 - Pressure to complete projects quickly
 - Staffing (TDD Only)
 - 8 Existing Vacancies 5-PM Eng. III's; 1-Sr. PM Eng. III; 2-Sr. PM Eng. IV's
 - 4 Pending Retirements Division Chief; 1 Eng. V Section Chief; 1 Eng. IV; 1 Planner II;
 - FCDOT Director retiring May 3, 2023!
 - New Political Climate at least 2 new Board members come November 2023!





Transportation Project Development A Locality's Perspective

• Challenges Ahead:







CONSULTANT SELECTION





Transportation Project Development A Locality's Perspective

Consultant Selection

• Process

- Professional Services Standard Qualifications Based Process
 - Defined by State Code Architecture, Engineering and Surveying
 - SF-330 Parts I & II
 - Request for Qualifications (RFQ) VDOT Template(s)
- Non-Professional/Consultant Services
 - Planning is considered a Consultant Service (Traffic Engineering is a Professional service)
 - Can/Could include price-based selection criteria





- What We ("I") Look for:
 - VDOT Experience particularly w/NOVA District
 - You are not just working for FCDOT, but for VDOT as well!
 - VDOT Locally Administered Project (LAP) Experience
 - In NOVA District in particular!
 - Personnel with VDOT LAP and Environmental Certifications
 - Technical Expertise of Personnel/Team
 - Matches FCDOT's Program and/or Project needs
 - Experience on projects that include:
 - Fairfax County SWM Ordinance and requirements
 - Land Development Services (LDS) review and approval processes





- What We ("I") Look for (cont.):
 - Include <u>Specific</u> Roles and Responsibilities of Personnel and Firm
 - Resumes and sample Projects Don't be George Santos!
 - Well thought out Organization Chart
 - Don't just throw lots of staff/sub-consultants and resumes into the SF-330
 - We Select People not just 'Firms'





- How we Distribute Work to On-Calls
 - Unique Aspects of the project Scope of Work
 - Technical requirements of the project
 - Familiarity with Project Area
 - Completed projects in vicinity of Project before
 - Familiar with anticipated project Stakeholders
 - Performance on Previous Task Orders
 - Workload
 - \$ of Task Orders to date
 - # of Task Orders to date





PROJECT DEVELOPMENT ISSUES QA/QC






- Project Development Issues QA/QC
 - FCDOT does not have technical experts in all fields
 - Ex: No Geotechnical or Structural Engineer on staff in FCDOT
 - We heavily rely on Consultants for QA/QC
 - Plan Development/Presentation should follow VDOT Standards
 - CADD Standards
 - Plan Assembly
 - Geometric Design Guidelines
 - Road Design Manual
 - Instructional & Information Memoranda (IIM's), etc.





- Project Development Issues QA/QC (cont.)
 - Avoid Plan Clutter
 - Requesting additional \$ to complete standard design tasks
 - AutoTurn, sight-distance, and/or stopping sight distance exhibits
 - Comment Resolution
 - Backcheck comment resolution form and actual plan sheets
 - Responses to comments are inadequate, unclear or lack sufficient detail
 - Comment resolution forms submitted AFTER the plan submittal
 - Erosion and Sediment Control
 - Reviewed and Approved by FCDOT (VDOT does not review)
 - Prepared Signed and Sealed by certified Consultant staff
 - E&S Phases should have same # of Phases as the MOT







- Project Development Issues QA/QC (cont.)
 - Curb Ramp Design & Details (CG-12's)
 - Follow VDOT I&IM/RDM requirements
 - Pedestrian vs. Bicycle wants and needs often conflict
 - Utilities
 - Test pit data on storm drain profiles and x-sections
 - Adding test pit data when additional test pits are required
 - Utility Service Lines
 - Water, Gas, Sanitary Sewer Laterals!!





- Project Development Issues QA/QC (cont.)
 - Estimates
 - Earthwork Summary for Phased Construction
 - VDOT Cost Estimating Workbook (CEWB)
 - Complete (all fields filled in)
 - Latest version (February 2023!)
 - Schedules input for PE, RW and CN in order to compute Inflation factors
 - Assumptions noted/explained
 - Backup/details of quantity takeoff(s)
 - Backup/details on source of Unit Prices and/or how derived
 - Appropriate Inflation and Contingency Factors





- Project Development Issues QA/QC (cont.)
 - Design Problems/Alternatives
 - You're the 'experts'
 - Propose solutions develop alternatives/options, do the analysis, and make a recommendation
 - Design Revisions/Progression
 - Changes to one part of design not followed through or coordinated with other disciplines that are impacted by the change
 - Drainage calcs./report updated but not the plans
 - Ex. Drainage calcs updated but Project Data Sheet not updated accordingly (nutrient credit requirements per calcs don't match plans)






- Project Development Issues QA/QC (cont.)
 - Technical/Misc. Issues
 - Ditches at top of retaining walls in cut slopes
 - Inlets not deep enough for UD-4's to tie in where undercut is required
 - Storm Drains Systems width of trench/work area not accounted for in setting construction limits, RW/Easement needs and/or impacts to existing features
 - Driveways
 - Slopes
 - Construction limits along driveways perpendicular to the roadway
 - Pavement sawcut lines on radii
 - Proposed fence lines on radii






Transportation Project Development












28




Transportation Project Development A Locality's Perspective








Transportation Project Development A Locality's Perspective







Transportation Project Development







Transportation Project Development A Locality's Perspective


Has computerization made us 'lazy' with design?

- Think before we put 'pen to paper'
- "Garbage in Garbage Out" (GIGO)
 - Just because the computer spits out an 'answer' doesn't make it the best solution.
- VDOT Road Design Manual Appendix A1, page A1-31
 "Gradients are to be computed to as few decimal places as possible and should be in numbers evenly divisible by four, where feasible."





Transportation Project Development







- Project Development Issues QA/QC (cont.)
 - Contract/Task Order Issues
 - Preparation and negotiating Task Orders taking too long. What is appropriate time frame? 2 months?
 - Requesting allowances or contingency to correct sub-standard work, address design comments, and/or complete design standard tasks
 - Not keeping up with and following VDOT guidance and directives (I&IM's)
 - Sidewalks/Trails at 1.5% cross slope
 - Temp. Rumble strips on two-way two-lane flagging operations (TMP)
 - Ped Facilities RDM Changes App. A(1) Section 2 (June 2022)
 - Be Proactive rather than Re-active





Transportation Project Development A Locality's Perspective

- Project Development Issues QA/QC (cont.)
 - Contract/Task Order Issues
 - Multiple submittals required to complete a plan milestone
 - 2-3 submittals required to get VDOT RW Authorization
 - 4-5 submittals required before getting clearance for VDOT LUP (100% Plans)
 - We want the Consultants "A Team" designing our project
 - We recognize Consultant workload and prioritization needs and issues but if "B" or "C" team is assigned to the project, increased oversight and QA/QC is needed.

(at no extra cost ⁽ⁱⁱⁱ⁾)





Questions? Comments?

Do we have time to move on?





PROJECT SPOTLIGHT

RICHMOND HIGHWAY BUS RAPID TRANSIT (RHBRT)



Department of Transportation 37




Richmond Highway Bus Rapid Transit





































North Kings Highway Intersection Improvements (@ Shields Ave)











North Kings Highway Intersection Improvements (@ Shields Ave)











Relationship between North and Southbound BRT stations









TYPICAL BRT STATION












TYPICAL BRT STATION

















Estimated Risk Adjusted Project Cost

Management/Engineering/CM/Startup		\$176.06M
Right-of-Way Acquisition		\$176.87M
Land Rights	\$165.59M	
Relocation Assistance	\$8.28M	
Vehicles (Electric Buses)		\$53.02M
Maintenance Facility		\$24.78M
Transitway Construction		\$432.18M
Stations	\$57.50M	
Roadway/In-Plan Utilities	\$345.78M	
Systems	\$28.90M	
Unallocated Contingency		<u>\$74.15M</u>

Total Project Estimate

\$937.05M 🔼







Design/RW Status

• Design

- Currently in Project Development
- 60% Plans Submitted
- Anticipate "Entry into Engineering"
- 80% Design Submittal
- 100% Design/Final Plans

• Right-of-Way Acquisition

- Broken into Groupings
- Groups 1-PT Total Takes and Relocations
- Groups PA-PD Partial Takes
- RW Acquisition Complete





April 2022 March/April 2023 June 2023 June 2024

June 2022 – Oct. 2025 Oct. 2023 – March 2026 March 2026







Utilities

Sanitary Sewer

- 30% Design Underway
- Separate/Advanced Construction Contract

Watermain Relocation – In-Plan

• 50% Plans under review

Private Utilities

- broke into Zones (A-F) from North to South
- Relocation to begin in Zone A and move southward
- Utility Relocation NTP
- Utility Relocation Complete

March 2024 February 2029







Contracting/Procurement

• Bus Maintenance Facility

- Bid Advertisement
- Construction NTP

• Vehicle Acquisition

- Issue Vehicle IFB
- Notice to Proceed
- Vehicle Delivery Complete

October 2026 January 2027

March 2028 September 2028 June 2031








Contracting/Procurement

- Construction Bid Advertisement
- Full Funding Grant Agreement (FFGA)
- Construction NTP
- Substantial Completion
- Begin Revenue Service



June 2026

August 2026

March 2030

July 2031



